No.	Items of work	Per	Rate	Quantity	Cost	Rates tendered
			Rs. a. p.	Rs.		
6	Providing and fixing 6" dia. cast iron pipes of Mysore Iron Works, Bhadravathi, including cost of pipe ..	R.ft.	2 0 0	36	72	
7	Jelly wood plug and iron rod with locking arrangements and necessary fittings, complete	Each	L. S.	..	14	
8	Removing and resetting old rough revetment including new jelly backing and wedging properly complete	C.yd.	0 12 0	9	7	
9	Earthwork refilling with lead and lift watering and tamping complete using available earth	C.yd.	0 2 0	106	13	
	Waste Weir.					
1	Earthwork excavation	C.yd.	0 4 0	99	25	
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	273	68	
3	Burnt brick in surki mortar ..	„	0 4 6	488	137	
4	Plastering with surki mortar ..	Sqr.	3 12 0	6.20	23	
5	Burnt stone slabs 6" thick dressed and fixed in surki mortar	S.ft.	0 7 6	333	166	
6	Earthwork for closing the gap of old weir including lead, watering and tamping etc., complete	C.yd.	0 4 0	80	20	
7	Rough stone work new	„	1 12 0	48	84	
8	Removing and resetting old stone revetment work with new jelly and wedging complete	„	0 12 0	31	23	

V. V. PATANKAR,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 27th June 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2 P.M. on Monday, 13th July 1936, for constructing corridors connecting the Administrative Block with Maternity and Out-patient Blocks of McGann Hospital at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Challan for having deposited Rs. 270 (Rupees Two Hundred and Seventy only), as earnest money, and be superscribed "Tender for constructing corridors connecting the Administrative Block with Maternity and Out-patient Blocks of McGann Hospital at Shimoga" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Enigneer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Works should be according to Departmental specifications.

14. Transfer of works to other parties or subletting of contracts is prohibited.

15. Monthly progress should not be less than Rs. 1,500 and the work should be completed by the end of October 1936.

16. C. I. Pipes and cement will be supplied by the Department and the cost with centage recovered.

Abstract estimate for constructing corridors connecting the Administrative Block with Maternity and Out-patient Blocks of the McGann Hospital at Shimoga.

Sl. No.	Items of work	Per	Rate as per estimate	Quantity	Rates tendere	
					In figures	In words
			Rs. a.p.			
1	Earthwork excavation and filling in basement with consolidation.	C.yd.	0 5 0	69		
2	Concrete stone jelly in surki mortar ..	C.ft.	0 5 0	936		
3	Size stone masonry in chunam including bond slabs	„	0 6 6	1,071		
4	Burnt stone slabs 6″ thick, 2 line dressed and fixed in chunam mortar including cement pointing 1 : 3 ..	S.ft.	1 0 0	232		
5	Cement pointing to basement 1 : 3 ..	Sqr.	4 0 0	2.41		
6	Red coloured cement flooring ½″ thick over 1½″ cement concrete (1 : 3 : 6), superimposed on 4″ stone jelly concrete in lime mortar, including cutting into lines, etc., complete ..	Sqr.	27 0 0	3.14		
7	Dismantling stone steps at the right side of Out-patient Dispensary and fixing on the external side of corridor	L. S.	..	..		
8	Dismantling and removing pillars in verandah of Administrative Block	No.	5 0 0	2		
9	Bonding masonry at junctions ..	L. S.	..	..		
10	Providing pillars with C. I. pipes 7″ dia. and 10′—9″ high with burnt stone capital slab (filling the pipes for one foot hight at bottom with cement concrete 1 : 3 and the rest with cement concrete 1 : 6) and constructing a skin wall with bricks alround C. I. pipes including plastering, etc., as per design ..	No.	45 0 0	9		
11	M. S. girders including carriage, hoisting, freight charges, etc., complete	Cwt.	12 0 0	20		
12	Boxing girders with brick in cement mortar 1 : 3 and exmet reinforcements and chunam plastering ..	R.ft.	0 12 0	107		
13	R. B. C. terrace with one course of ordinary bricks laid edgewise in cement mortar 1 : 2½ and cement concrete 1 : 2 : 4, 2″ between bricks and on top of bricks with reinforcements both longitudinal and crosswise, and					

Sl. No.	Items of work	Per	Rates as per estimate	Quantity	Rate tendered	
					In figures	In words
			Rs. a. p.			
	over which 3″ to 6″ thick, brick kappi in unslaked quick lime and 2 coats of colas to be laid and 2 courses of flat tiles in lime mortar and surfaces both top and bottom chunam plastered and white washed twice	Sqr.	80 0 0	5·50		
14	Burnt brick parapet 9″ thick and 2′ feet high including nice plastering as per design	R.ft.	1 0 0	107		
15	9″ brick cornice as per design ..	,,	0 12 0	107		
16	Painting girders boxed, with two coats of silver grey paint	Sqr.	4 8 0	3·21		
17	C. I. ornamental rain center spouts as per design	No.	10 0 0	6		

N. SUBBA RAO,
Executive Engineer.

MEDICAL DEPARTMENT

OFFICE OF THE SECRETARY, VICTORIA, MINTO OPHTHALMIC AND VANI VILAS HOSPITALS, BANGALORE.

Abstract Notification dated the 18th June 1936.

Notice is hereby given that sealed tenders (in triplicate) on half sheet foolscap size paper will be received by the undersigned at his office (Victoria Hospital) at 11 A.M., on Monday, the 20th July 1936 for Washing the Linen of the Victoria Hospital, Bangalore, from 1st August 1936 to 30th June 1937. For further particulars, please refer to the notification published in pages 927-928, Part VI of the *Mysore Gazette*, dated the 25th June 1936.

H. N. PALLEGAR,
Secretary.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE *EX-OFFICIO* CONTROLLER OF PATENTS AND DESIGNS, BANGALORE.

No. C2 Pat. 123—35-36, *dated 22nd June* 1936.

NOTICE OF ACCEPTANCE OF APPLICATION FOR PATENT.

No. 123—35-36 *of 31st December* 1935.

Notice is hereby given that all persons interested in opposing the grant of a patent on the application referred to below may at any time within 3 months of the date of his notification give notice to the *Ex-officio* Controller of Patents and Designs in Mysore, in the prescribed form No. 5 of such opposition.

"Improvements in treating Sugar" by Pedro Sanchery of 14 Requena Street, Havana.

Any one desiring to inspect copy of the Specification of the above may call at the Office of the *Ex-officio* Controller of Patents and Designs on any working day between 11 A.M. and 5 P.M. A sum of rupee one will be charged for such inspection.

S. ABDUL WAJID,
Ex-officio *Controller of Patents and Designs.*